


BERTH DATA SHEET

FAIRLIE QUAY



PARTICULARS/BASIC INFORMATION

Admiralty Chart No.	1867 Plan D	Survey Drawing No	Nil
Min. Depth Alongside	10m outer, 6m inner	Fendering	See Comments
Quay Design	Piled Jetty	Avg Water Density	1025 kg/m ³
Latitude	55-46.0N	Longitude	004-51.8W
Quay length overall	188m out 100m long	Eastings/Northings	220466 / 656304
No of berths	2	SWL Bollards	20T
Max vessel LOA	160m outer, 80m inner	Avg bollard spacing	15m
Max vessel beam	12m	Line of the berth	176° / 356°
Air Draught restrictions	Nil	Quayside SWL	8t/m ³
ISPS Status	ISPS compliant	Height of cope edge*	4.6m

*from Chart Datum

QUAYSIDE FACILITIES – BY PRIOR ARRANGEMENT

Fresh Water	Yes	Shore Power	Yes, subject to connections
Port Waste	Yes	Cranes	20t crane available for hire

BERTH DATA SHEET

FAIRLIE QUAY



TIDAL INFORMATION – BASED ON Millport

HAT	3.86m	MHWS	3.39m
MHWN	2.83m	MLWN	1.06m
MLWS	0.44m	LAT	-0.04m
Comments			

BERTH OPERATOR

NAME Fairlie Quay Marina	CONTACT DETAILS Main Road Fairlie, Ayrshire Scotland, KA29 0AS VHF Ch 80 Tel: 01475 568267 Fax: 01475 568410 Email: enquire@fairliequay.co.uk
--------------------------	---

COMMENTS:

Fendering consists of hardwood with Rubber facings.